



Apex House LEFA Business Park Edgington Way Sidcup Kent DA14 5BH

www.apexlifts.com

Ref: RQ68361

1st August 2014

Fax:

Mr Simon O'Connor Rydon Charles Park Dartford Greenhithe Kent DA9 9AY

Dear Simon,

Re: Grenfell Tower – Lifts H090 & H091 New Landing Entrances

Further to your request and my subsequent site visit, I now have pleasure in submitting the following quotation to supply and install complete new landing entrances for the new Walkway and Mezzanine floors for your consideration.

I trust this meets with your approval and look forward to hearing from you in due course.

Lifts H090 & H091 New Landing Entrances Walkway & Mezzanine Floors

To supply and install the following equipment

LANDING DOORS	Stainless steel sliding door panels.
EMERGENCY RELEASE	Each entrance shall be equipped with emergency unlocking aperture.
LANDING THRESHOLD	landing sill installed at each level.
LANDING ENTRANCE	Install unit type landing entrance assembly at each floor comprising sliding stainless steel doors, door guides, spring closers, door bottom suspension equipment, top tracks, door Interlocks and box section entrance surround entrance finishes
FASCIA PANELS	Provide within the lift well, flush sheet steel shaft fascia panels between bottom track and top of landing door-frame below.
LANDING CALL BUTTONS	Flush mounted call stations comprising of up/down directional buttons mounted in a faceplate with integral call acceptance illumination.





Registered in England No. 1129631 Apex Lift & Escalator Engineers Ltd







LANDING INDICATORS	Provide dot matrix digital type car position indicator mounted within flush mounted faceplate.
CAR CONTROLS	Install new walkway and mezzanine floor push buttons in both the horizontal and vertical car operating panels.
CONTROL PANEL	Update control panel software and provide modified drawings.
WIRING	Installation to be wired using multi strand PVC insulated wire enclosed within steel conduit and trunking. Flexible conduit to be used where adjustment is required or vibration may occur
DELIVERY PERIOD	Based on current commitments delivery shall be executed in 8-10 weeks from order
INSTALLATION PERIOD	To be completed within 4 weeks, subject to our continued and uninterrupted working.
PRICE	To carry out the supply and installation of 4 No. lift entrances our price will be £43,205.00 excluding VAT
BUILDERS WORKS	We have included for backfilling the landing Architraves only. All other builders works such as cutting out the new landing entrances and cutting out apertures for the landing push buttons and landing position indicators to be carried out by others.

Our proposal is exclusive of value added tax and is subject to our standard terms and conditions.

This quotation is to carry out the works within normal working hours.

As a valued client of *APEX LIFTS*, we endeavour to provide a flexible approach to all your lift requirements.

In the meantime, if *APEX LIFTS* or myself can be of any further assistance, or you would like to know about any of the products or services that we can provide, please do not hesitate to contact me at my office on 020 8300 2929.

Yours sincerely,

Ray Morray.

Ray Murray Service Sales Consultant