

## 2A.77 Witness Inspection Points

Witness Inspection Points are to be available to the SO with a minimum of 3 days notice by the Contractor:

1. Witness inspection of the lift controller under test at the Contractor's Works.
2. Witness inspection of lift car with doors and operator fitted at Contractor's Works.
3. Witness inspection of site readiness.
4. Witness inspection of guide rails with alignment equipment still in position.
5. Witness inspection of machine room after fixing positions of controllers, machines etc.
6. Witness inspection of car, sling, counterweight and diverters and alignment.
7. Witness inspection of main roping and compensation arrangements.
8. Witness inspection of safety gear and all pit equipment.
9. Witness inspection of compensation and governor ropes.
10. Witness inspection of entrance frames and sills prior to building in.
11. Witness inspection of hangers, tracks, doors, closers and locks complete.
12. Witness inspection of architraves, prior to building in.
13. Witness inspection of tubed and trunked lift car, complete with doors and operator.
14. Witness inspection of trailing flexes hung and connected.
15. Witness inspection of shaft and landing equipment, installed and wired.
16. Witness inspection of machine room trunking and conduits, etc. before floor screed is laid.
17. Witness inspection of wired electrical equipment in the machine room.
18. Witness inspection of cleaned down shaft, painting, screens, builders work and lift ready for test.
19. Witness inspection of commissioning tests.
20. Witness inspection of items complete and handover.

The Tenderer shall allow and include for all SO attendances and costs for off site witness tests.