

THE GRENFELL TOWER INQUIRY

EXHIBIT JDE/5

This is the Exhibit marked “JDE/5”
referred to in the witness statement
of Jonathon David Earl



R J Electrics Ltd

Electrical Contracting Engineers

Tel : [REDACTED]

Fax : [REDACTED]



J S Wright & Co Ltd
Mr D Peacock

02nd December 2015

Dave,

Re: Grenfell Tower - secondary power supply from Grenfell Walk

As now confirmed by Max Fordham Associates the existing secondary power supply currently fed from the adjacent Testerton Walk premises does not meet current IET regulations and as such cannot be used for the new Grenfell Tower smoke extract system.

The next option proposed is to provide an up-rated 40A power supply from the closer switch room in the adjacent Grenfell Walk premises. A preliminary survey of the current Grenfell Walk main intake arrangements has identified that adding the additional power supply will not affect the building's current power usage and therefore is acceptable to proceed.

Therefore as requested please find our quotation to design, supply and install a new 40A TP&N secondary power supply from Grenfell Walk to serve the new smoke extract system in Grenfell Tower.

Cost:

To supply & install a new 40A TP&N supply from the Grenfell Walk building intake.

The new supply is to be installed using Pirelli FP600 fire rated SWA cable routed on steel cable tray containment.

Total cost: £9,406.80

Regards,

Andy Bridges