

GRENFELL WINDOW SURROUNDS

	A	B	C	D	E
1	<u>DESCRIPTION OF ITEM</u>	<u>NO OF WINDOWS PER FLOOR</u>	<u>COST PER WINDOW</u>	<u>COST PER FLOOR</u>	<u>GENERAL NOTES</u>
2					
3	remove existing frame place plasterboard backer to gain margin and close cavity.	32	£189.30	£6,057.60	all access arranged by Rydon
4					
5	place celotex insulation to reveals and basd of window		NO OF FLOORS	19	all furniture and belongings removed by others prior to works commencing including curtains etc.
6					
7	place white plastic capping board to sides and heads and mastic		TOTAL COST	£115,094.40	all skips by Rydon
8					
9	place plastic capping board to remaining cill section which terminates into reveals		ON SITE WORKING SUPERVISOR	£5,700.00	access via internal lift
10					
11	plastic trim to underside of the cill to cover existing timber, mastic all areas on completion.		TOTAL CONTRACT VALUE	£120,794.40	access required to two properties at any one time.
12					
13	clear all areas on completion				no fitting of curtain batterns etc allowed at this point
14					
15	pre surveys to be carried out to fully assess prior to starting SDP and Rydon, and sign off sheet produced on completion with SDP and Rydon.				storage supplied by Rydon,
16					
17					cutting will take place in the most at ground level but we will require a area on the floor adjacent to lifts for storage and minor cutting, this area will be managed with barriers and sings but will not restrict tennat access into units or lifts.
18					
19					power by Rydon, most will be battery operated tools but we will need to Hoover and clean